

One Information Way, Suite 225

Little Rock, AR 72202

501-945-4506 ■ 800-365-4506 ■ Fax: 501-945-7718

www.tarcoroofing.com



TECHNICAL BULLETIN LB-07-06B-R1

Fast90® Tile Underlayment - Application Update

This bulletin reiterates some of the essential considerations when staging tiles on LeakBarrier® Fast90® self-adhering tile underlayment. This technical bulletin is effective April 12, 2010.

As we enter into the summer months, the following guidelines must be strictly followed to eliminate the possibility of sheet tearing and/or tile slippage, caused by improper tile stacking.

- After installation of Fast90, it is important to wait a minimum of 48 hours before roof loading of tiles.
- All tiles shall be staged, (two tiles perpendicular to slope, four tiles on top parallel to slope), not to exceed 6-high, to the standard maximum roof pitch of 5:12 for flat tiles and 6:12 for lugged tiles. At roof slopes greater than the abovementioned limitations, "Loading Battens" or "Toe Boards" should be used for loading tiles. (See tile staging method below).

Illustration of the Tile Staging Method



Front View - Staged Tiles



Side View - Staged Tiles

If Fast90 published installation instructions and the above guidelines are not strictly followed, Tarco will not be responsible for the product performance.

If you have any questions or require additional information, please contact your local Tarco sales representative or email Tarco Technical Services at technicalservice@tarcoroofing.com